

Installation of JUPITER IDEAL system between existing joist application



Existing joists battened and lined with ply 30mm below top of joist. IDEAL panels cut to fit tightly between.



Flow and return pipes as well as circuit pipes channelled through joists.



Schotten & Hansen timber floors installed directly over existing floor joists.



Jupiter Edge Zone (EZ) panels used to provide 3 pipes per joist void.



T&G Screed Replacement tiles laid directly on top of System panels (separating foil protects pipes from glue). Tiles act as load bearing surface for final stone floor.